

10100 | Visual Display Boards

940	10120 Tack & Visual Aid Boards		CREW	DAILY OUTPUT	LABOR-HOURS	UNIT	2003 BARE COSTS				TOTAL INCL O&P	940
							MAT.	LABOR	EQUIP.	TOTAL		
2300	Glass enclosed cabinets, alum., cork panel, hinged doors											
2400	3' x 3', 1 door		2 Carp	12	1,333	Ea.	445	42		487	560	
2500	4' x 4', 2 door			11	1,455		740	46		786	890	
2600	4' x 7', 3 door			10	1,600		1,200	50.50		1,250.50	1,400	
2800	4' x 10', 4 door			8	2		1,550	63		1,613	1,800	
2900	For lights, add per door opening		1 Elec	13	615		150	23		173	201	
3100	Horizontal sliding units, 4 doors, 4' x 8' 8' x 4'		2 Carp	9	1,778		2,425	56		2,481	2,775	
3200	4' x 12'			7	2,286		3,100	72		3,172	3,525	
3400	8 doors, 4' x 16'			5	3,200		3,925	101		4,026	4,475	
3500	4' x 24'			4	4		5,125	126		5,251	5,850	
9000	Minimum labor/equipment charge			4	4	Job		126		126	210	

10150 | Compartments & Cubicles

100	10155 Toilet Compartments		CREW	DAILY OUTPUT	LABOR-HOURS	UNIT	2003 BARE COSTS				TOTAL INCL O&P	100
							MAT.	LABOR	EQUIP.	TOTAL		
0010	PARTITIONS, TOILET											
0100	Cubicles, ceiling hung, marble		2 Marb	2	8	Ea.	1,425	248		1,673	1,975	
0200	Painted metal		2 Carp	4	4		430	126		556	680	
0250	Phenolic			4	4		820	126		946	1,125	
0300	Plastic laminate on particle board			4	4		560	126		686	825	
0500	Stainless steel			4	4		1,075	126		1,201	1,375	
0600	For handicap units, incl. 52" grab bars, add						320			320	355	
0800	Floor & ceiling anchored, marble		2 Marb	2.50	6,400		1,550	199		1,749	2,050	
1000	Painted metal		2 Carp	5	3,200		390	101		491	600	
1050	Phenolic			5	3,200		865	101		966	1,125	
1100	Plastic laminate on particle board			5	3,200		630	101		731	865	
1300	Stainless steel			5	3,200		1,225	101		1,326	1,525	
1400	For handicap units, incl. 52" grab bars, add						273			273	300	
1600	Floor mounted, marble		2 Marb	3	5,333		920	166		1,086	1,275	
1700	Painted metal		2 Carp	7	2,286		370	72		442	525	
1750	Phenolic			7	2,286		875	72		947	1,075	
1800	Plastic laminate on particle board			7	2,286		520	72		592	690	
2000	Stainless steel			7	2,286		1,275	72		1,347	1,525	
2100	For handicap units, incl. 52" grab bars, add						273			273	300	
2200	For juvenile units, deduct						37.50			37.50	41	
2400	Floor mounted, headrail braced, marble		2 Marb	3	5,333		875	166		1,041	1,225	
2500	Painted metal		2 Carp	6	2,667		390	84		474	570	
2550	Phenolic			6	2,667		840	84		924	1,075	
2600	Plastic laminate on particle board			6	2,667		735	84		819	945	
2800	Stainless steel			6	2,667		1,225	84		1,309	1,500	
2900	For handicap units, incl. 52" grab bars, add						273			273	300	
3000	Wall hung partitions, painted metal		2 Carp	7	2,286		495	72		567	665	
3300	Stainless steel			7	2,286		1,200	72		1,272	1,450	
3400	For handicap units, incl. 52" grab bars, add						273			273	300	
4000	Screens, entrance, floor mounted, 58" high, 48" wide											
4100	Marble		2 Marb	9	1,778	Ea.	575	55		630	725	
4200	Painted metal		2 Carp	15	1,067		177	33.50		210.50	251	
4300	Plastic laminate on particle board			15	1,067		415	33.50		448.50	510	
4500	Stainless steel			15	1,067		650	33.50		683.50	770	