

# Exterior Doors and Windows

Aluminum Window		Unit	Material	Labor	Equip.	Total	Specification
38" x 37", 3 Light	Demolish	Ea.		15.15		15.15	Cost includes material and labor to install 38" x 37" three light awning, double glazed aluminum window including screen.
	Install	Ea.	320	93.50		413.50	
	Demolish and Install	Ea.	320	108.65		428.65	
	Remove and Install	Ea.		74.80		74.80	
	Clean	Ea.	.04	6.55		6.59	
	Minimum Charge	Job		187		187	
38" x 53", 3 Light	Demolish	Ea.		22		22	Cost includes material and labor to install 38" x 53" three light awning, double glazed aluminum window including screen.
	Install	Ea.	515	93.50		608.50	
	Demolish and Install	Ea.	515	115.50		630.50	
	Remove and Install	Ea.		74.80		74.80	
	Clean	Ea.	.06	7.85		7.91	
	Minimum Charge	Job		187		187	
50" x 37", 4 Light	Demolish	Ea.		22		22	Cost includes material and labor to install 50" x 37" four light awning, double glazed aluminum window including screen.
	Install	Ea.	525	93.50		618.50	
	Demolish and Install	Ea.	525	115.50		640.50	
	Remove and Install	Ea.		74.80		74.80	
	Clean	Ea.	.06	7.85		7.91	
	Minimum Charge	Job		187		187	
50" x 53", 4 Light	Demolish	Ea.		22		22	Cost includes material and labor to install 50" x 53" four light awning, double glazed aluminum window including screen.
	Install	Ea.	865	107		972	
	Demolish and Install	Ea.	865	129		994	
	Remove and Install	Ea.		85.49		85.49	
	Clean	Ea.	.07	9.20		9.27	
	Minimum Charge	Job		187		187	
63" x 37", 5 Light	Demolish	Ea.		22		22	Cost includes material and labor to install 63" x 37" five light awning, double glazed aluminum window including screen.
	Install	Ea.	675	107		782	
	Demolish and Install	Ea.	675	129		804	
	Remove and Install	Ea.		85.49		85.49	
	Clean	Ea.	.07	9.20		9.27	
	Minimum Charge	Job		187		187	
63" x 53", 5 Light	Demolish	Ea.		22		22	Cost includes material and labor to install 63" x 53" five light awning, double glazed aluminum window including screen.
	Install	Ea.	930	107		1037	
	Demolish and Install	Ea.	930	129		1059	
	Remove and Install	Ea.		85.49		85.49	
	Clean	Ea.	.09	11.20		11.29	
	Minimum Charge	Job		187		187	
Mullion Bars	Install	Ea.	8.90	30		38.90	Includes labor and material to install mullions for sliding aluminum window.
	Minimum Charge	Job		187		187	
Glass Louvered 2' x 2'	Demolish	Ea.		15.15		15.15	Cost includes material and labor to install 2' x 2' aluminum window including 4" glass louvers, hardware, screen.
	Install	Ea.	45.50	68		113.50	
	Demolish and Install	Ea.	45.50	83.15		128.65	
	Remove and Install	Ea.		54.40		54.40	
	Clean	Ea.	.02	4.90		4.92	
	Minimum Charge	Job		187		187	